



Notes:

1. 32 MPa Concrete Strength @ 28 days
2. Concrete contains MacMatrix 2" Fibers
3. Lid sealed with Conseal CS-665
4. 3 - 24" Polylok Lids
5. Tank Weight: 11,280 LBS
6. Lid Weight: 6500 LBS
7. Tank Volume: 1700igal (1162/538)
8. Also available in reverse model

DAN'S
Pre-Cast
LTD.

6100 Scott Rd.
Duncan, B.C.
250-746-7400
www.dansprecast.com

**1700 IMP. GAL. PUMP
(7728 LITRES)**

DATE: JUNE 18, 2018

DRAWN BY: EJG